

RFB#ITARC-452 CAP Riverside Audio/Video Installation

Bid Recap RFB #ITARC-452 Closing Date 5/25/2017	On Target	IES Commercial, Inc.	Vector Resources d/b/a VectorUSA
CSLB / DIR	787362 / 1000002459	910798 / 1000000679	654046 / 1000002893
Labor	\$22,760.00	\$24,866.00	\$18,243.50
Materials	\$60,555.71	\$66,630.84	\$56,641.62
Tax (8.75%)	\$5,298.62	\$5,830.20	\$4,956.14
All Others	\$650.00	\$0.00	\$1,171.20
Base Bid	\$89,264.33	\$97,327.04	\$81,012.46
Contingency (10% of Base Bid)	\$8,926.43	\$9,732.70	\$8,101.25
Project Cost With Contingency	\$98,190.77	\$107,059.74	\$89,113.71
Payment Terms	Progress Payments	Progress Payments	Progress Payments
* Apparent Low Cost Provider			
* Pending Further Analysis			