## Project Name: Harmony Haven Fiber Backbone Upgrade

## Document G - Material List

It is the contractor's responsibility to insure all labor and material needed to deliver a complete, fully functional system that complies with all applicable codes, RCIT and industry standards / best practices is accounted for in their cost proposal. The following is not intended to be a complete material list, but a clarification on certain items specified within the scope of services in Appendix A.

LG
Chief
C2G
Leviton

Sound Masking Equipment		
Gold All Inclusive Unit	A1U	Lencore
i.Net Speaker, brushed Aluminum housing, RJ45 Universal chain	G545-U	Lencore
IR Touch Pad Controller, Wall Plate, RJ45	G41	Lencore
20' Patch Cords White Plenum	20FPCC6	Lencore
Category 6 High-Flex Patch Cords 5' White	6H460-05W	Leviton
Category 6 Berk-Tek LM UTP, CMP, Box, White	10032092	Berk-Tek

Access Control Equipment		
PW - Power SuppA61:C75ly for PW5K2ENC1 and PW5K2ENC2	PW7KPSU120	Honeywell
PW - 7000 Intelligent Controller	PW7K1IC	Honeywell
PW - Series Daisy Chain Cable	PW5K1DCC	Honeywell
PW - 7000 Single Reader Board	PW7K1R1	Honeywell
PW - Series Dual Reader Module	PW7K1R2	Honeywell
PW - 7000 Input Module	PW7K1IN	Honeywell
PW - 7000 Output Module	PW7K1OUT	Honeywell
PW - Reader License 64 Doors	PWRDR64	Honeywell
PW - Reader License 32 Doors	PWRDR32	Honeywell
PW - Software User License	PW45SWCL	Honeywell
YUSA - 12V 7AH Battery	NP7-12	YUSA
PW - Wall Mount Enclosure	PW5KENC1	Honeywell
HID - Reader	40NKS-00-01CF1M	HID
HID - Reader	20NKS-00-01CF1M	HID
Altronix - Power supply	AL600ULACM	Altronix
Alarm Controls - Lock Down	RP-44	Alarm Controls
Alarm Controls - Door Release	TS-18	Alarm Controls

Axis Outdoor Camera 2mp	P3265-LV	Axis
Axis Outdoor Camera 2mp	P3265-LVE	Axis
BCD Server	PN - BCD-QUO134438377375-JACINTO	BCD Video
Capture - 19" Monitor	OE-19VGHDMI2	Capture
Vanco - HDMI Cable 8'	USCP08	Vanco